



CURRENT PROJECT - MIXER VESSEL

Project : Prototfuel & Fit For Use Mixer Vessel

Client : Control & Application Pte Ltd , Foster Wheeler Pte Ltd

End User : Exxonmobil Jurong Island , Singapore Parallel Train Project

Material Construction : A240 GrSS304L

Design : ASME Sec VIII Div 1

3rd Party : ABS NDT : PMI , RT , UT , Copper Sulphate Solution Test & Dye Penetrant Test

Total Quantity : 28 Units Pressure Vessels

Operating Pressure : 150 PSIG

Mixer : Impeller Type , Brand : Mixtec Australia

Finishing : Special Coating and Insulation with Pyrogel

Construction Lead Time : 90 Working Days

Contract Value : SGD750,000.00

